



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Change Order

Date	Change Order #
9/7/2022	1000

Name / Address

Project

City of Smyrna
P. O. Box 1226
Smyrna, Ga. 30081

Fieldwood Drive 3307/ 3309 Drainage

Description	Unit	Qty	Unit Price	Total
Storm Drainage Improvements 3305, 3307 & 3309 Fieldwood Drive				
RETAINING WALL				
- Demolition and Disposal of Existing Timber Wall	L.S.	1	2,850.00	2,850.00
- Excavate and Haul Off Spoils/ Dirt and Existing Backfill for Retaining Wall and Grade to Drain.	L.S.	1	2,200.00	2,200.00
- Install Timber Retaining Wall (6 x 6" Pine) Approximately 3 to 4 ft. Back from Face of Existing Timber Retaining Wall. Including: 1. Drainage and Foundation Materials. 2. Place Deadman as Required	S.F.	240	59.25	14,220.00
- Timber Steps, Approximately (9) Nine 6 x 6" Timber Steps with Walls on Each Side, 4 ft. Wide	S.F.	56	76.50	4,284.00
LANDSCAPE				
- Permanent Grassing (Tiff Tuff Bermuda), Prepped and Installed	S.F.	1,000	2.00	2,000.00
- Permanent Grassing (Zeon Zoysia), Prepped and Installed	S.F.	2,250	2.60	5,850.00
- Permanent Grassing (Fescue Sod), Prepped and Installed	S.F.	1,000	2.95	2,950.00
- Pine Straw Bale Installed	EA	12	8.75	105.00
- Landscape Allowance, This Allowance is for the Following Plant List and Quantity Only:	L.S.	1	2,400.00	2,400.00
- 10 Hostas				
- 20 Day Lillies				
- 2 Patio Peach Trees				
- 5 Purple Secretia				
- 7 Big Blue Leroioe				
- Privacy Tree Allowance (Installed) Cryptomeria - 15 Gallon, 8' Avg. Height	EA	3	675.00	2,025.00
- Privacy Tree Allowance (Installed) Cryptomeria - 30 Gallon, 12' Avg. Height	EA	3	950.00	2,850.00

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Change Order Total:



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Change Order

Date	Change Order #
9/7/2022	1000

Name / Address

Project

City of Smyrna
P. O. Box 1226
Smyrna, Ga. 30081

Fieldwood Drive 3307/ 3309 Drainage

Description	Unit	Qty	Unit Price	Total
HARDSCAPE - 5 ft. Wide x 30 ft. Long Path to Match Neighbor, Strip Rubble Edging (Tan/Buff), Decorative Gravel (Egg Rock) and 18 x 18" Step Stones (Flagstone)	S.F.	150	26.90	4,035.00
- Provide Labor Only for the Removal of the Lower Pool of the Water Feature and Remove Existing Pump and Place Existing Pump Up to the Next Tier Pool.	L.S.	1	1,725.00	1,725.00
DRAINAGE AND IRRIGATION - Connect Three (3) Existing Downspouts to a Main Trunk Line. Main Trunk Line to be Connected to 6" Connection at Existing Storm Drain Drop Inlet.	L.S.	1	2,350.00	2,350.00
- Drip Line Addition: Tie Into Existing Drip Line, Approximately 75 L.F. of New Drip Line with Emitters Included.	L.S.	1	350.00	350.00
ELECTRICAL - Remove and Reinstall weather resistant receptacle onto new retaining wall. Wiring placed in conduit from grill station to wall.	L.S.	1	975.00	975.00
Total:				51,169.00
- Contingency (10 %)	L.S.	1	5,116.90	5,116.90
NOTE: 1. All landscape plants and sod are to be free of disease at time of installation and have a 30 day disease free warranty. 2. Sod is not warrantied against Army Ants. 3. Customer is responsible for providing water after installation. Contractor will water in all newly installed plants the day of installation only. 4. Any work not shown in the scope will be considered additional work and contractor will price at that time. 5. Fencing Repairs and/ or Replacements by Others.				

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Change Order Total: \$56,285.90