

Need a P.O. → 40144501-541500-42201
(per Eric Randall)



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
3/22/2022	942

Name / Address

City of Smyrna P. O. Box 1226 Smyrna, Ga. 30081

Project

Fieldwood Drive 3307/ 3309 Drainage

Description	Qty	Unit	Unit Price	Total
Storm Drainage Improvements 3307 & 3309 Fieldwood Drive				
- Grading Complete	1	L.S.	7,800.00	7,800.00
- 6 ft. Wood Privacy Fence Removal and Replacement	1	L.S.	950.00	950.00
- Install/ Repair Timber Retaining Wall Section	150	S.F.	56.65	8,497.50
1. Pressure Treated 6 x 6" Pine				
2. Box out around proposed drainage structure approximately 5' from face of wall deep and 5' wide and 4' tall.				
3. Footer - Install # 57 stone base				
4. Place deadman as required				
5. Includes Drainage for Wall				
6. Not Responsible for Existing Wall Failures				
- 48" Doghouse Manhole (6 to 8ft. Depth)	1	L.S.	9,600.00	9,600.00
- 18" HDPE	12	L.F.	192.00	2,304.00
- Precast Concrete Drop Inlet Manhole with 2 x 3 ft. Grate & Frame	1	EA	4,800.00	4,800.00
- Permanent Grassing (SOD)	2,000	S.F.	2.25	4,500.00

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total:

\$38,451.50

5284